
ENDANGERED HABITATS CONSERVANCY HANSON PONDS RUSSIAN RIVER FLOODPLAIN RESTORATION PROJECT



December, 2020



GENERAL NOTES

- 1. PROJECT REQUIRES A CLASS A GENERAL ENGINEERING CONTRACTOR'S LICENSE IN THE STATE OF CALIFORNIA.
- 2. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO THE COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO THE CONSTRUCTION MANAGER. CONTRACTOR IS RESPONSIBLE FOR VISITING THE SITE AND BECOMING FAMILIAR WITH THE SITE CONDITIONS PRIOR TO BIDDING, SHOULD EXISTING CONDITIONS DIFFER FROM THOSE SHOWN OR INDICATED, OR F IT APPEARS THAT THESE PLANS, AND SPECIFICATIONS DO NOT ADEQUATELY DETAIL THE WORK TO BE DONE, CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER PRIOR TO CONTINUING WITH ANY RELATED WORK, NO ALLOWANCE WILL BE MADE ON CONTRACTOR'S BEHALF FOR ANY EXTRA EXPENSE RESULTING FROM FAILURE OR NEGLECT IN DETERMINING THE CONDITIONS UNDER WHICH WORK IS TO BE
- 3. NOTED DIMENSIONS TAKE PRECEDENCE OVER SCALE.
- 4. QUANTITIES OF ITEMS, LENGTH OF PROJECT, AND SITE CONDITIONS SHOWN IN THE PLANS ARE APPROXIMATE, ALL MATERIALS SHALL BE FURNISHED AND INSTALLED BY
- 5. CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT. INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS: AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIEY, AND HOLD THE CITY, GHD, AND THEIR REPRESENTATIVES HARMLESS FROM ANY AND ALL LIABILITY, REAL ANDIOR ALLEGED, IN CONJUNCTION WITH THE PERFORMANCE OF THIS PROJECT.
- CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY AND ALL DAMAGES TO EXISTING STRUCTURES, ROADS, PARKING AREAS, AND UTILITIES DURING CONSTRUCTION.
 ALL DAMAGE SHALL BE RESTORED TO AN "AS GOOD OR BETTER" CONDITION AT THE CONTRACTOR'S EXPENSE.
- 7. A SET OF SIGNED CONSTRUCTION DRAWINGS AND SPECIFICATIONS WILL BE KEPT AT ALL TIMES AT THE JOB SITE ON WHICH ALL CHANGES OR VARIATIONS IN THE WORK. INCLUDING ALL EXISTING UTILITIES, ARE TO BE RECORDED AND/OR CORRECTED DAILY AND SUBMITTED TO THE CONSTRUCTION MANAGER WHEN THE WORK TO BE DONE
- 8. CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 72 HOURS IN ADVANCE OF COMMENCEMENT OF ANY PART OF THE WORK AND SHALL COORDINATE
- THE DESIGN FEATURES INCLUDING HORIZONTAL AND VERTICAL ALIGNMENTS, SECTIONS, AND ALL DESIGN DETAILS SHOWN ON THESE DESIGN PLANS SHALL NOT BE ALTERED OR MODIFIED IN ANY WAY DURING CONSTRUCTION WITHOUT THE EXPRESSED, WRITTEN DIRECTION AND APPROVAL OF THE CONSTRUCTION MANAGER. DRAINAGE STRUCTURES SHALL BE INSTALLED AS SHOWN ON THE PLANS WITH ONLY MINOR CORRECTIONS IN LOCATION SKEW, ANDIOR ELEVATIONS AS NEEDED TO FIT FIELD CONDITIONS AS DETERMINED BY THE CONSTRUCTION MANAGER.
- 10. THE CONTRACTOR SHALL READ AND MAKE CAREFUL EXAMINATION OF THE PLANS, SPECIFICATIONS, QUANTITIES AND MATERIAL ESTIMATES AND VISIT THE SITE OF THE PROPOSED CONSTRUCTION TO BECOME FAMILIAR WITH THE SITE CONDITIONS AND LIMITATIONS BEFORE MAKING A BID. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL ERRORS RESULTING FROM THE FAILURE TO MAKE SUCH AN EXAMINATION. ANY INFORMATION DERIVED FROM THE MAPS, PLANS, SPECIFICATIONS, PROFILES, DRAWINGS OR FROM THE ENGINEER WILL NOT RELIEVE THE CONTRACTOR FROM ANY RISK OR FROM FULFILLING THE TERMS OF THE CONTRACT
- 11. NO WORK SHALL BE PERFORMED OUTSIDE OF THE APPROXIMATE LIMITS OF DISTURBANCE SHOWN ON THE PLANS WITHOUT THE APPROVAL OF THE CONSTRUCTION
- 12. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING STAGING AREAS AND EXTENTS WITH THE CONSTRUCTION MANAGER.
- 13. UNLESS OTHERWISE NOTED, THE CONTRACTOR SHALL PROTECT EXISTING SURVEY MONUMENTS WITHIN WORK LIMITS. ANY MONUMENT DAMAGED BY THE CONTRACTOR SHALL BE RESET IN ACCORDANCE WITH THE CALIFORNIA PROFESSIONAL LAND SURVEYORS ACT AT THE CONTRACTORS SOLE EXPENSE.
- 14. WHENEVER ANY MATERIAL OR EQUIPMENT IS INDICATED OR SPECIFIC BY PATENT OF PROPRIETARY NAME OR BY THE NAME OF THE MANUFACTURER, SUCH SPECIFICATION SHALL BE CONSIDERED AS USED FOR DESCRIBING THE MATERIAL OR EQUIPMENT DESIRED AND SHALL BE CONSIDERED AS FOLLOWED BY THE WORDS "OR APPROVED EQUAL". THE CONTRACTOR MAY OFFER ANY MATERIAL OR EQUIPMENT WHICH SHALL BE EQUAL IN EVERY RESPECT TO THAT SPECIFIED; PROVIDED THAT WRITTEN APPROVAL FIRST IS OBTAINED FROM THE CONSTRUCTION MANAGER.
- 15. ANY INFORMATION DERIVED FROM THE MAPS, PLANS, SPECIFICATIONS, PROFILES, DRAWINGS OR FROM THE CONSTRUCTION MANAGER WILL NOT RELIEVE THE TRACTOR FROM ANY RISK OR FROM FULFILLING THE TERMS OF THE CONTRACT.
- 16. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER UPON DISCOVERING DISCREPANCIES, ERRORS OR OMISSIONS IN THE PLANS OR SITE NDITIONS. PRIOR TO PROCEEDING, THE DISCREPANCY SHALL BE RESOLVED TO THE SATISFACTION OF THE CONSTRUCTION MANA
- 17. CONTRACTOR SHALL MAINTAIN DAILY COMMUNICATIONS WITH THE CONSTRUCTION MANAGER TO DISCUSS DETAILS OF IMPLEMENTATION, ORDER OF WORK, METHODS OF MINIMIZING ENVIRONMENTAL IMPACTS AND OTHER RELEVANT COMPONENTS OF CONSTRUCTION, CONTRACTOR AND CONSTRUCTION MANAGER SHALL MEET MINIMUM WEEKLY ON-SITE TO DISCUSS PROJECT DETAILS,
- 18. THE CONTRACTOR SHALL COMPLETELY REVIEW, BE FAMILIAR WITH, UNDERSTAND AND ADHERE TO THE TERMS OF ALL PERMITS AND AGENCY APPROVALS FOR THIS PROJECT. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW AND UNDERSTAND THE CONDITIONS RELEVANT TO THE CONSTRUCTION ACTIVITIES. A COPY OF ALL PROJECT PERMITS SHALL REMAIN ONSITE AT ALL TIMES.
- 19. NO SHUTDOWN OF THE PROJECT SITE IS ANTICIPATED, HOWEVER, UNFORESEEABLE CONDITIONS INCLUDING BUT NOT LIMITED TO FIRE, GEO-HAZARD CONDITIONS, OR PRECIPITATION COULD REQUIRE THE CONSTRUCTION MANAGER TO SUSPEND CONSTRUCTION ACTIVITIES AT ALL OR PART OF THE SITE FOR SAFETY REASONS AT NO COST TO THE CITY OR THEIR REPRESENTATIVES.
- 20. ALL EQUIPMENT AND PERSONNEL SHALL ACCESS THE CORRIDOR VIA THE CONSTRUCTION ENTRANCES AND ACCESS ROUTES SHOWN ON THE PLANS
- 21. CONTRACTOR SHALL BE AWARE THE PROJECT IS LOCATED ON PRIVATE LANDS AND CITY RIGHT-OF-WAY AND THEREFORE ALL ACTIVITIES SHALL REMAIN WITHIN LIMITS HOWN ON PLANS AND ALL ADVANCEMENT WITHIN THE LIMITS SHALL BE PRE-AUTHORIZED BY THE CONSTRUCTION MANAGER
- 22. CONSTRUCTION ACCESS ROUTES AND EQUIPMENT STAGING AREAS SHALL BE LIMITED TO THE LIMITS OF CONSTRUCTION DISTURBANCE AS SHOWN ON THE PLANS, CONSTRUCTION ACTIVITIES SHALL BE PROHIDITED FROM UNINECESSARLY DISTURBING AQUATIC HABITAT AND WETLANDS, DISTURBANCE SUCH AS EXCAVATION, FILLING OR DEWATERING OF ANY EXISTING DITCHES, CHANNELS AND OTHER PONDED WATER AREAS SHALL OCCUR AFTER THE AREA HAS BEEN SEINED AND CLEARED BY A QUALIFIED BIOLOGIST, PROCURED BY OTHERS, THE CONTRACTOR SHALL COOPERATE WITH THE BIOLOGIST IN THE COLLECTION AND RELOCATION EFFORTS.
- 23. THE CONTRACTOR SHALL RESTORE TEMPORARY HAUL ROADS AND STAGING AREAS AT THE CONCLUSION OF USE THROUGH BLADING, RIPPING OR OTHERWISE REMOVING RUTS, DE-COMPACTING AND NATURALIZING TO PRE-CONSTRUCTION CONDITIONS. THE CONSTRUCTION MANAGER/MONITOR RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO REPAIR DAMAGE WHERE HAUL ROADS AND STAGING AREAS WERE CONSTRUCTED.
- 24. BIOLOGIST PROVIDED BY OTHERS (NIC) SHALL IDENTIFY ALL AREAS OF NESTING BIRDS PRIOR TO ANY CONSTRUCTION DISTURBANCE (FEBRUARY 15 AUGUST 15). CONTRACTOR TO MAINTAIN APPLICABLE SETBACKS.

SURVEY NOTES

- 1. TOPOGRAPHIC DATA SHOWN HEREON IS BASED ON DATA PROVIDED BY NOAA, 2019.
- 2. HORIZONTAL DATUM IS NAD 83, STATE PLANES, ZONE II.
- 3. VERTICAL DATUM IS NAVD 88.
- 4. UNDERGROUND UTILITIES SHOWN HEREON WERE LOCATED FROM ABOVE GROUND VISUAL UTILITY STRUCTURES, NO UTILITY RESEARCH WAS CONDUCTED FOR THIS PROJECT.
- PROPERTY LINE AND EASEMENT PLOTTING IS BASED ON A PRELIMINARY TITLE REPORT DATED JANUARY 13, 2014, PREPARED BY CHICAGO TITLE COMPANY, TITLE NO. 10-495107061-D-KF.
- SEE ADDITIONAL SURVEY NOTES ON SHEET G-103.

DESIGN NOTES

- 1. FLOODPLAIN DESIGN COMPLETED BY NOAA FISHERIES & USGS PER NOVEMBER 2016 FEASIBILITY STUDY.
- 2. SEASONAL LOW GROUNDWATER ELEVATIONS PROVIDED BY LUHDORFF & SCALMANNI CONSULTING ENGINEERS (LSCE 2020).
- 3. REVEGETATION DESIGN COMPLETED BY H.T. HARVEY & ASSOCIATES (NOVEMBER 2020).
- 4. GEOTECHNICAL ENGINEERING RECOMMENDATIONS PROVIDED BY MILLER PACIFIC ENGINEERING GROUP (MPEG 2020).

WATER MANAGEMENT NOTES

- 1. CONTRACTOR SHALL SUBMIT A WATER MANAGEMENT PLAN IN CONFORMANCE WITH THE PROJECT PERMITS AND IN ACCORDANCE WITH
- 2. CONTRACTOR SHALL COOPERATE WITH THE AQUATIC BIOLOGIST DURING THE AQUATIC SPECIES RELOCATION.

DEFINITION OF "LIMITS" AS SHOWN ON THE PLAN

LIMITS OF GRADING: INDICATES APPROXIMATE LIMIT OF PERMANENT GRADING OR LAND DISTURBANCE (EXCAVATION OR FILLING),

LIMITS OF DISTURBANCE: INDICATES APPROXIMATE LIMITS OF TEMPORARY CONSTRUCTION DISTURBANCES AND INCLUDES POTENTIAL ACCESS ROUTES, STAGING AREAS, AND STOCKPILE AREAS THAT SHALL BE RESTORED BACK TO PRE-CONSTRUCTION CONDITIONS.

UTILITY NOTES

- 1. UTILITIES INCLUDING UNDERGROUND GAS, SANITARY SEWER, STORM SEWER, DRINKING WATER, COMMUNICATIONS, AND ABOVE GROUND DRAINAGE AND ELECTRICAL ARE KNOWN TO EXIST WITHIN THE LIMITS OF DISTURBANCE.
- 2. LOCATIONS OF EXISTING UTILITIES AND STRUCTURES ARE FROM THE BEST INFORMATION AVAILABLE. EXACT LOCATION AND COMPLETENESS ARE NOT GUARANTEED, CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICES ALERT (800) 227-2600 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION AND POTHOLE FOR EXACT LOCATION, NOTIFY THE CONSTRUCTION MANAGER IMMEDIATELY IF LOCATE INDICATES THAT EXISTING UTILITIES ARE DIFFERENT THAN SHOWN ON DRAWINGS.
- 3. LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE PLOTTED FROM INTERPOLATION OF PHYSICAL EVIDENCE ON THE SITE SURFACE, ALL UTILITIES ARE SUBJECT TO FIELD VERIFICATION BY THE CONTRACTOR.
- 4. ALL LOCATIONS FOR WORK SHALL BE CHECKED AND COORDINATED WITH EXISTING CONDITIONS IN THE FIELD BEFORE BEGINNING CONSTRUCTION UNDER THIS SECTION OR ANY OTHER SECTION.
- 5. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO UTILITIES. FEATURES. AND STRUCTURES LOCATED ON THE SITE. LOCATE. PROTECT, AND AVOID DISRUPTION OF ALL ABOVE AND BELOW GRADE UTILITIES DURING CONSTRUCTION, UNLESS STATED
- 6. CONSTRUCTION ACTIVITY WILL TAKE PLACE IN THE VICINITY OF ABOVE GROUND AND UNDERGROUND ELECTRIC TRANSMISSION LINES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO BE AWARE OF, AND OBSERVE, THE MINIMUM CLEARANCES FOR WORKERS AND EQUIPMENT OPERATING NEAR HIGH VOLTAGE ELECTRIC LINES AS SET OUT IN THE HIGH VOLTAGE SAFETY ORDERS OF THE CALIFORNIA DIVISION OF INDUSTRIAL SAFETY AS WELL AS OTHER APPLICABLE SAFETY REGULATIONS.
- 7. CONSTRUCTION ACTIVITY WILL TAKE PLACE IN THE VICINITY OF GAS LINES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO BE AWARE OF, AND OBSERVE, THE MINIMUM CLEARANCES FOR WORKERS AND EQUIPMENT OPERATING NEAR GAS LINE AS SET OUT IN THE SAFETY ORDERS OF THE CALIFORNIA DIMISION OF INDUSTRIAL SAFETY AS WELL AS OTHER APPLICABLE SAFETY REGULATIONS.
- 8. ALL UTILITY CONSTRUCTION SHALL CONFORM TO CITY STANDARDS, UTILITY PROVIDOR REQUIREMENTS, AND CURRENT CALIFORNIA
- 9. ALL EXISTING UTILITIES AND TIE-IN POINTS SHOULD BE CONSIDERED ACTIVE UTILITIES UNLESS OTHERWISE INDICATED.

GRADING NOTES

- CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION STAKING AND SHALL ARRANGE FOR STAKING, STAKING WILL BE REVIEWED BY THE CONSTRUCTION MANAGER FOR CONFORMANCE TO DESIGN PRIOR TO CONSTRUCTION.
- 2. ALL GRADES BETWEEN SPOT AND CONTOUR ELEVATIONS SHALL HAVE UNIFORM SLOPE UNLESS OTHERWISE INDICATED. MAINTAIN
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL CONSTRUCTION, ADEQUATE SHORING BRACING, TIES, AND
- 4. ALL EXISTING LANDSCAPED AND UNPAYED AREAS WHICH ARE DISTURBED OUTSIDE LIMITS OF GRADING BY CONSTRUCTION OR ARTHWORK OPERATIONS SHALL BE RETURNED TO AS GOOD OR BETTER CONDITIONS.
- 5. ALL DITCHES, SWALES, GUTTERS, ETC, SHOULD BE CONSIDERED ACTIVE STORM CONVEYANCES UNLESS OTHERWISE INDICATED. CONTRACTOR IS RESPONSIBLE FOR ADDRESSING STORM WATER DRAINAGE AND DEWATERING OF WORK AREAS DURING
- 6. PERFORM GRADING IN ACCORDANCE WITH THE LATEST EDITION OF THE CALIFORNIA BUILDING CODE AND APPLICABLE HUMBOLDT
- 7. THE CONTRACTOR SHALL BE AWARE OF THE SOFT AND SATURATED SOIL CONDITION THAT MAY BE ENCOUNTERED DURING THE CONSTRUCTION.
- 8. IN THE EVENT CULTURAL RESOURCES (I.E., HISTORICAL, ARCHAEOLOGICAL, AND PALEONTOLOGICAL RESOURCES, AND/OR HUMAN REMAINS) ARE DISCOVERED DURING CONSTRUCTION ACTIVITIES. WORK SHALL BE HALTED. A QUALIFIED ARCHEOLOGIST SHALL BE PROVIDED BY THE CITY FOR AN ON-SITE EVALUATION. IF HUMAN BURIALS OR HUMAN REMAINS ARE ENCOUNTERED, THE CONTRACTOR SHALL ALSO NOTIFY THE COUNTY CORONER.
- 9. SHOULD GRADING OPERATIONS ENCOUNTER HAZARDOUS MATERIALS, OR WHAT APPEAR TO BE HAZARDOUS MATERIALS, STOP WORK THE AFFECTED AREA IMMEDIATELY AND CONTACT THE CONSTRUCTION MANAGER OR THE APPROPRIATE AGENCY FOR FURTHER
- 10. ALL CONSTRUCTION SITES AND HAUL ROADS SHALL BE MAINTAINED, AS NECESSARY, TO MINIMIZE THE EMISSION OF DUST AND PREVENT CREATION OF NUISANCE TO ADJACENT PROPERTIES,
- 11. ALL STAGING/STOCKPILE AREAS WHICH ARE DISTURBED BY CONSTRUCTION OR EARTHWORK OPERATIONS SHALL BE RETURNED TO
- 12. DURING WET WEATHER PERIODS, CONTRACTOR IS RESPONSIBLE FOR SEQUENCING CONSTRUCTION IN A MANNER TO MINIMIZE MPACT ON OPEN EARTHWORK AND COMPACTION OPERATIONS.

30% DESIGN

Date

NOTE: PLANSET CONTENT COLOR-DEPENDENT; PLANSET TO BE PLOTTED IN FULL COLOR

original size sheet 0 1


Bar is one inch on


Reuse of Documents This document and the ideas and designs incorporate herein, as an instrument of professional service, is the property of GHD and shall not be reused in whole or in par for any other project without GHD's written authorization. © 2020 GHD





		00 /0 DEGICIT
Drawn C. PENNY	Designer C. PENNY	Client ENDANGERED HABITATS CONSERVANCY Project HANSON RUSSIAN RIVER FLOODPLAIN RESTORATION PROJECT
Drafting J. SVEHLA Check	Design Check 8. ALLEN	Title NOTES
Project Manager J. SVEHLA	Date 12/3/2020	Project No. 11195953
This document shall not be used for construction unless signed and sealed for construction.	Scale NO SCALE	Original Size ANSI D Sheet No. G-002 Sheet 2 of 20





SHEET LIST TABLE SHEET NUMBER SHEET G-001 TITLE SHEET G-002 NOTES 2 G-003 SYMBOLS, ABBREVIATIONS, AND SHEET LIST 4 G-004 EROSION MANAGEMENT NOTES AND DETAILS G-005 EROSION MANAGEMENT PLAN 5 G-101 MONITORING WELL AND SURVEY CONTROL G-102 ZONING AND LAND USE PLAN G-103 EXISTING CONDITIONS G-104 CONSTRUCTION PHASING SCHEDULE 9 G-105 EXISTING HABITATS CIVIL C-101 SITE PLAN, ACCESS, AND SHEET INDEX 12 C-102 PLAN VIEW 1 OF 3 C-103 PLAN VIEW 2 OF 3 14 C-104 PLAN VIEW 3 OF 3 C-201 PROFILES 1 OF 2 15 16 C-202 PROFILES 2 OF 2 C-301 CROSS SECTIONS 1 OF 2 17 18 C-302 CROSS SECTIONS 2 OF 2 19 C-401 REVEGETATION PLAN

C-402 REVEGETATION TYPICAL SECTION

SHEET INDEX

		FG	FINISH GRADE	N	NORTH	S	SOUTH	UBC	UNIFORM BUILDING CODE
AB	AGGREGATE BASE	F/L	FLOW LINE	(N)	NEW	SCH	SCHEDULE	UG	UNDERGROUND
AC	ASPHALTIC CONCRETE	FT.	FOOT OR FEET	NIC	NOT IN CONTRACT	SD	STORM DRAIN	UGT	UNDERGROUND TELEPHONE
ACI	AMERICAN CONCRETE INSTITUTE	FI	FOOT OR FEET	NO	NUMBER NUMBERING	SECT	SECTION	UNK	UNKNOWN
ACP	ASBESTOS CEMENT PIPE	G	GAS	NOM	NOMINAL	SHT	SHEET	UNO	UNLESS NOTED OTHERWISE
ACW	ACTIVE CHANNEL WIDTH	GA	GAGE	NTS	NOT TO SCALE	SIM	SIMILAR	UNO	UNLESS NOTED OTHERWISE
AGG	AGGREGATE	GAL	GALLON	NIS	NOT TO SCALE	SL	SLOPE	V	VENT. VOLT. VALVE
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	GALV	GALVANIZED	oc	ON CENTER	SPEC	SPECIFICATIONS	VC	VERTICAL CURVE
APN	ASSESSOR'S PARCEL NUMBER	GB	GRADE BREAK	OD	OUTSIDE DIAMETER	SQ	SQUARE	VERT	VERTICAL
APPROX	APPROXIMATE	GPM	GALLONS PER MINUTE	OF	OUTSIDE FACE, OVERFLOW	SQ FT	SQUARE FOOT	VEICE .	VERTICAL
ВС	BEGIN CURVE	GUY	GUY WIRE	OHE	OVER HEAD ELECTRIC	SQIN	SQUARE INCH	W	WATER
BF	BANK FULL	GVL	GRAVEL	OPNG	OPENING	SS	SANITARY SEWER	W/	WITH
BM	BENCH MARK			OR	OFFICIAL RECORDS	SST	STAINLESS STEEL	WM	WATER METER
BP	BEGIN POINT	HCD	HIMBOI DT COUNTY DECORES		ST. ISSE RECORDS	SSCO	SANITARY SEWER CLEANOUT	WP	WATERPROOF
BVC	BEGIN VERTICAL CURVE	HCR	HUMBOLDT COUNTY RECORDS	P	PROPOSED	STA	STATION	ws	WATER SURFACE
SVCE	BEGIN VERTICAL CURVE ELEVATION		HIGH DENSITY POLYETHYLENE	PE	PERMANENT EASEMENT	STD	STANDARD	WSE	WATER SURFACE ELEVATION
	DEGIN FEATIONE GUILTE ELEVATION	HGT	HEIGHT	PG&E	PACIFIC GAS & ELECTRIC	STL	STEEL STEEL PIPE	WSP	WELDED STEEL PIPE
CFS	CUBIC FEET PER SECOND	HMA	HOT MIX ASPHALT	PL	PLATE, PROPERTY LINE	STR	STRAIGHT	WTR	WATER
CJ	CONSTRUCTION JOINT	HOR	HORIZONTAL	PP	POWER POLE	STRUCT	STRUCTURE	WWF	WELDED WIRE FABRIC
CLR	CLEAR	ID	INSIDE DIAMETER	PRCST	PRECAST	SIRUCI	STRUCTURE		
CM	CONSTRUCTION MANAGER	IN	INCH	PREFAB	PREFABRICATED			XFMR	TRANSFORMER
CMU	CONCRETE MASONRY UNIT	INV	INVERT	PRESS	PRESSURE			XING	CROSSING
CONC	CONCRETE	INV	INVERT	PROP	PROPERTY	T	TANGENT	YD	YARD
CONN	CONNECTION	JP	JOINT UTILITY POLE	PSF	POUNDS PER SQUARE FOOT	TC	TOP OF CURB	YR	YEAR
CONT	CONTINUOUS, CONTINUATION	JT	JOINT	PSI	POUNDS PER SQUARE INCH	TCE	TEMPORARY CONSTRUCTION EASEMENT	IN	TEAR
COORD	COORDINATE	31	JOINT	PSIG	POUNDS PER SQUARE INCH POUNDS PER SQUARE INCH, GAUGE	TECH	TECHNICAL	8	AND
CTD	CENTERED	KIP	THOUSAND POUNDS	PVC	POLYVINYL CHLORIDE PLASTIC	TEL	TELEPHONE	@	AT
CTR	CENTER	Kii	THOUSAND FOUNDS	PVI	POINT OF VERTICAL INTERSECTION		TEMPORARY	Ø	DIAMETER
CF	CUBIC FOOT	a	LEFT, LENGTH	PVMT	PAVEMENT	TEMP	THICK	6	CENTER LINE
CY	CUBIC YARD	LB	POUNDS	PVMI	PAVEMENT	THK	TOP OF WALL	P	PROPERTY LINE, PLATE
		LF	LINEAR FEET			TYP	TYPICAL TYPICAL	(E)	EXISTING
DR	DRAIN	LG	LONG			ITP	TTPICAL	(P)	PROPOSED
DI	DROP INLET	LONG	LONGITUDINAL	R, RAD	RADIUS			(N)	NEW
DIA	DIAMETER	LONG	LONGITUDINAL	RC	REINFORCED CONCRETE			(14)	NEW
DW	DRIVEWAY			RCB	REINFORCED CONCRETE BOX				
DWG	DRAWING	MAX	MAXIMUM	REF	REFER, REFERENCE				
(E)	EXISTING	MFR	MANUFACTURER	REINF	REINFORCED, REINFORCING, REINFORCE				
EA	EACH	MH	MANHOLE	REQD	REQUIRED				
EC	END CURVE	MIN	MINIMUM, MINUTE	ROW	RIGHT OF WAY				
EG	EXISTING GROUND	MISC	MISCELLANEOUS	RSP	ROCK SLOPE PROTECTION				
EL. ELEV	ELEVATION		MONUMENT						
ELEC	ELECTRIC, ELECTRICAL	MSNRY	MASONRY						
ENGR	ENGINEER	MTL	MATERIAL						
EP	END POINT	MWS	MAXIMUM WATER SURFACE						
EQ	EQUAL								
EQ SP	EQUALLY SPACED								
EQPT	EQUIPMENT								
ESM	ENGINEERED STREAMBED MATERIAL								
EXC	EXCAVATE								
EXP	EXPOSED, EXPANSION								

30% DESIGN

			+	
			+	
4			+	
			+	
0.	Issue	Drawn	Approved	Date

NOTE:
PLANSET CONTENT
COLOR-DEPENDENT;
PLANSET TO BE PLOTTED
IN FULL COLOR





				OU /O D E OI OI
	Drawn C. PENNY	Designer C. PENNY	Client ENDANGERED HABITATS CONSERVANCY	ODATION DDO IEC
	Drafting Check J. SVEHLA	Design Check 8. ALLEN	Project HANSON RUSSIAN RIVER FLOODPLAIN REST	
	Project Manager J. SVEHLA	Date 12/3/2020	Project No. 11195953	
١	This document shall not be used for construction unless signed and sealed for construction.		Original Size ANSI D Sheet No. G-003	Sheet 3 of 20

EROSION, SEDIMENT, POLLUTION, & WASTE CONTROL NOTES


- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MINIMIZE EROSION AND PREVENT THE TRANSPORT OF SEDIMENT TO THE ADJACENT RIVER AND SENSITIVE AREAS.
- PERFORM EROSION PREVENTION AND SEDIMENT CONTROL IN ACCORDANCE WITH THE LATEST EDITION OF CHAPTER 33 OF THE CALIFORNIA BUILDING CODE, APPLICABLE SONOMA COUNTY REGULATIONS, AND SECTION 20 OF THE CALTRANS STANDARD SPECIFICATIONS.
- 3. AT A MINIMUM, THE CONTRACTOR SHALL EMPLOY THE FOLLOWING BEST MANAGEMENT PRACTICES (BMPS) AS DESCRIBED IN THE CURRENT CALTRANS STORM WATER QUALITY HANDBOOK AS NEEDED:

SS-2 PRESERVATION OF EXISTING VEGETATION SS-6 REDWOOD MULCH SS-10 OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES NS-2 DEWATERING OPERATIONS NS-3 PAVING AND GRINDING OPERATIONS

NS-5 CLEAR WATER DIVERSION

WM-1 MATERIALS DELIVERY AND STORAGE WM-2 MATERIAL LISE VM-4 SPILL PREVENTION AND CONTROL WM-8 CONCRETE WASTE MANAGEMENT WM-9 SANITARY/SEPTIC WASTE MANAGEMENT


- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIX ANY EROSION, SEDIMENT, POLLUTION, & WASTE CONTROL DEFICIENCIES IDENTIFIED BY THE OWNER OR THE OWNERS REPRESENTATIVE.
- 5. PRIOR TO FINAL ACCEPTANCE ALL AREAS OF THE SITE WILL BE VEGETATED OR PERMANENTLY STABILIZED AND ALL TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE REMOVED.
- IF DISCREPANCIES OCCUR BETWEEN THESE NOTES, MATERIAL REFERENCED HEREIN OR MANUFACTURERS RECOMMENDATIONS, THEN THE MOST PROTECTIVE SHALL APPLY.
- 7. THE OWNER IS RESPONSIBLE FOR OBTAINING AND COMPLYING WITH THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT WASTE DISCHARGE REQUIREMENTS FOR DISCHARGES OF STORM WATER RUNOFF ASSOCIATED WITH CONSTRUCTION ACTIVITY. THE SITE DISTURBANCE IS GREATER THAN 1 ACRE, THEREFORE THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH THE STORMWATER POLLUTION PREVENTION
- 8. PRESERVATION OF EXISTING VEGETATION SHALL OCCUR TO THE MAXIMUM EXTENT PRACTICABLE.
- 9. DISCHARGES OF POTENTIAL POLLUTANTS FROM CONSTRUCTION SITES SHALL BE PREVENTED USING SOURCE CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SEDIMENT, TRASH, NUTRIENTS, PATHOGENS, PETROLEUM HYDROCARBONS, METALS, CONCRETE, CEMENT, ASPHALT, LIME, PAINT, STAINS, GLUES, WOOD PRODUCTS, PESTICIDES, HERBICIDES, CHEMICALS, HAZARDOUS WASTE, SANITARY WASTE, VEHICLE OR EQUIPMENT WASH WATER AND CHLORINATED WATER.
- 10. WHENEVER IT IS NOT POSSIBLE TO UTILIZE EROSION PREVENTION MEASURES, EXPOSED SLOPES SHALL EMPLOY SEDIMENT CONTROL DEVICES, SUCH AS FIBER ROLLS AND SILT FENCES. FIBER ROLLS AND SILT FENCES SHALL BE TRENCHED AND KEYED INTO THE SOIL AND INSTALLED ON CONTOUR. SILT FENCES SHALL BE INSTALLED APPROXIMATELY 2 TO 5 FEET FROM TOE OF SLOPE.
- 11. THE CONTRACTOR SHALL PROTECT STORM DRAIN INLETS FROM POTENTIAL POLLUTANTS UNTIL DRAINAGE CONVEYANCE SYSTEMS ARE FUNCTIONAL, THE SITE IS STABILIZED, AND CONSTRUCTION HAS BEEN COMPLETED.
- 12. ENERGY DISSIPATERS SHALL BE INSTALLED AT STORM DRAIN OUTLETS WHICH MAY CONVEY STORM WATER FLOW LEADING TO SOIL EROSION.
- SOIL AND MATERIAL STOCKPILES SHALL BE PROPERLY PROTECTED TO MINIMIZE SEDIMENT AND POLLUTANT TRANSPORT FROM THE CONSTRUCTION SITE.
- 14. SOLID WASTE, SUCH AS TRASH AND DEBRIS, SHALL BE PLACED IN DESIGNATED COLLECTION AREAS OR CONTAINERS. THE CONSTRUCTION SITE SHALL BE CLEARED OF SOLID WASTE DAILY, OR AS NECESSARY, AND REGULAR REMOVAL AND PROPER DISPOSAL SHALL BE ARRANGED.
- 15. PROPER APPLICATION, CLEANING AND STORAGE OF POTENTIALLY HAZARDOUS MATERIALS, SUCH AS PAINTS AND CHEMICALS, SHALL BE CONDUCTED TO PREVENT THE DISCHARGE OF POLLUTANTS.
- 16. WHEN UTILIZED, TEMPORARY RESTROOMS AND SANITARY FACILITIES SHALL BE LOCATED AND MAINTAINED TO PREVENT THE DISCHARGE OF POLLUTANTS.
- 17. APPROPRIATE VEHICLE STORAGE, FUELING, MAINTENANCE AND CLEANING AREAS SHALL BE DESIGNATED AND MAINTAINED TO PREVENT DISCHARGE OF POLLUTANTS.
- 18. ENTRANCE(S) TO THE CONSTRUCTION SITE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF POTENTIAL POLLUTANTS OFFSITE. POTENTIAL POLLUTANTS DEPOSITED ON PAVED AREAS WITHIN THE COUNTY RIGHT-OF-WAY, SUCH AS ROADWAYS AND SIDEWALKS, SHALL BE PROPERLY DISPOSED OF EACH WORKING DAY OR MORE FREQUENTLY AS NECESSARY.
- 19. CHANGES TO THE STORM WATER POLLUTION PREVENTION PLAN MAY BE MADE TO RESPOND TO FIELD CONDITIONS. CHANGES SHALL BE NOTED ON THE PLAN WHEN MADE.



NOTES:

- FILTER FABRIC SHALL BE INSTALLED IN A CONTINUOUS ROLL TO AVOID THE USE OF JOINTS, WHERE JOINTS ARE NECESSARY SPLICE FABRIC
 TOGETHER ONLY AT A SUPPORT POST WITH A MINIMUM 6" OVERLAP. SECURELY FASTEN BOTH ENDS TO THE POST.
- 2. POSTS SHALL BE SPACED A MAXIMUM OF 6' APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 12".
- 3. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4" WIDE AND 6" DEEP ALONG THE LINE OF POSTS UPHILL FROM THE BARRIER, TRENCH SHALL FOLLOW THE CONTOUR.
- 4. TRENCH SHALL BE BACKFILLED WITH NATIVE MATERIAL.
- 5. INSPECT AND REPAIR AFTER EACH RAINFALL. INSPECT DAILY DURING PROLONGED RAINFALL.
- 6. REMOVE SEDIMENT WHEN IT REACHES APPROXIMATELY ONE THIRD THE HEIGHT ABOVE GROUND PORTION OF THE FENCE,
- ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE FILTER FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE AND SEEDED.






NOTES:

- 1. ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC ROADWAY
- 2. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS MUST BE REMOVED IMMEDIATELY.
- ACCESSES SHALL BE INSPECTED MONTHLY AND AFTER EACH RAINFALL WITH MAINTENANCE PROVIDED AS NECESSARY.






NOTES:

- CONTRACTOR SHALL INSPECT WATTLES WEEKLY AND AFTER EACH RAINFALL REPLACE WATTLES WHEN THEY HAVE DECOMPOSED, COLLAPSED. OR BEEN DAMAGED, REMOVE SEDIMENT FROM BEHIND THE WATTLE WHEN IT REACHES ONE INCH OF DEPTH.
- 2. WATTLES SHOULD BE PLACED ON THE CONTOUR AND IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT WATTLE.
- 3. THE DIRECTION OF RUNOFF FLOW TO THE WATTLES SHOULD BE PERPENDICULAR TO THE STAKED WATTLE LOCATION.
- 4. REMOVE UPON COMPLETION OF CONSTRUCTION SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.







30% DESIGN

Date

PLANSET CONTENT COLOR-DEPENDENT; PLANSET TO BE PLOTTED IN FULL COLOR


Bar is one inch or original size sheet Reuse of Documents


This document and the ideas and designs incorporate herein, as an instrument of professional service, is the property of GHD and shall not be reused in whole or in par for any other project without GHD's written authorization. © 2020 GHD





Drawn G. PENNY	Designer	C. PENNY	
Drafting J. SVEHLA	Design Check	8. ALLEN	
Project Manager J. SVEHLA	Date	12/3/2020	
This document shall not be used for		AS SHOWN	


Project H	NDANGERED HABITATS CONSERVANCY ANSON RUSSIAN RIVER FLOODPLAIN RESTOR ROSION MANAGEMENT NOTES AND DETAIL		I PF	≀OJ	EC
Project No.	11195953				
Original Size ANSI D	Sheet No. G-004	Sheet	4	of	20









































	Revegetation Zone—Target Habitats							
Revegetation Method	Floodplain Seasonal Wet Meadow	Floodplain Aquatic Backwater Pool and Channel	Floodplain Freshwater Marsh	Lower Slope Riparian Scrub	Mid-Slope Riparian Forest	Upper Slope Upland Riparian Forest		
Seeding of herbaceous wetland species	х	x	х	Х				
Seeding of herbaceous upland species					X	X		
Seeding of acoms and California buckeye			.02.26.1	1001 1001 1001 1001	х	х		
Sod (rootmat) translocation1	Х		Х					
Vegetative sprigging ¹	Х		Х					
Cuttings		22011.002.0011.002.0011.002.0		X				
Livewood transplants ¹				Х	Х	Х		
Container plants	Danie Danie Danie II				X	X		


REVEGETATION METHODS BY ZONE AND TARGET HABITATS

Scientific Name	Common Name
Floodplain and Lower Slope Wetland He	rbaceous Species Seed Mix
Artemisia douglasiana	California mugwort
Bidens frondosa	Sticktight
Carex barbarae	Valley sedge
Cyperus eragrostis	Tall cyperus
Eleocharis macrostachya	Spike rush
Elymus triticoides	Beardless wild rye
Epilobium ciliatum	Slender willow herb
Hordeum brachyantherum	Meadow barley
Juncus balticus	Baltic rush
Persicaria punctata	Dotted smartweed
Mid- and Upper Slope Upland Herbaceou	us Species Seed Mix
Amsinckia intermedia	Common fiddleneck
Amsinckia menziesii	Fiddleneck
Clarkia gracilis ssp. sonomensis	Sonoma clarkia
Elymus glaucus	Blue wildrye
Epilobium brachycarpum	Willow herb
Hemizonia congesta ssp. leucocephala	Hayfield tarweed
Hemizonia congesta ssp. lutescens	Hayfield tarweed
Lupinus bicolor	Bicolored lupine
Madia elegans	Common madia
Madia sativa	Coastal tarweed
Melica californica	California melic
Stipa pulchra	Purple needle grass

PLANT SPECIES PALETTES FOR SEEDING WETLAND AND RIPARIAN HABITATS

Scientific Name	Common Name
Artemisia douglasiana	California mugwort
Bolboschoenus fluviatilis	River bulrush
Carex barbarae	Valley sedge
Eleocharis macrostachya	Spike rush
Elymus triticoides	Beardless wild rye
Euthamia occidentalis	Western goldenrod
Juncus balticus	Wire rush
Schoenoplectus acutus	Hardstem bulrush
Schoenoplectus californicus	California bulrush
Scirpus microcarpus	Small fruited bulrush

PLANT SPECIES PALETTE FOR SOD TRANSLOCATION AND VEGETATIVE SPRIGGING TO RESTORE SEASONAL WET MEADOW AND FRESHWATER MARSH HABITATS



FLOODPLAIN RESTORATION CONCEPTUAL SECTION

		Revegetatio	n Zone—Tar	get Habitats
Scientific Name	Common Name	Lower Slope Riparian Scrub	Mid-Slope Riparian Forest	Upper Slope Upland Riparian Forest
Acernegundo	Box elder		X	
Aesculus californicus	California buckeye		X	X
Alnus rhombifolia	White alder	X		
Arbutus menziesii	Pacific madrone		X	X
Calycanthus occidentalis	Spicebush		X	
Comus sericea	American dogwood		X	
Populus fremontii	Fremont cottonwood	X	X	
Quercus agrifolia	Coast live oak			X
Rhododendron occidentale	Western azalea		X	
Salix exigua	Narrowleaf willow	X		
Salix laevigata	Red willow	X	X	
Salix lasiolepis	Arroyo willow	X	X	
Umbellularia californica	California bay		×	X
Vitis californica	California grape		X	

LIVEWOOD TRANSPLANT SPECIES PALETTE FOR RIPARIAN SCRUB, RIPARIAN FOREST, AND UPLAND RIPARIAN FOREST

Scientific Name	Common Name		
Acernegundo	Box elder		
Aesculus californica	California buckeye		
Baccharis pilularis	Coyote brush		
Fraxinus latifolia	Oregon ash		
Juglans hindsii	Northern California black walnut		
Populus fremontii	Fremont cottonwood		
Quercus agrifolia	Coast live oak		
Quercus kelloggii	Black oak		
Quercus lobata	Valley oak		
Rosa californica	California wild rose		
Rubus ursinus	California blackberry		
Salix laevigata	Red willow		
Salix lasiolepis	Arroyo willow		
Sambucus nigra	Blue elderberry		
Umbellularia californica	California bay laurel		

CONTAINER PLANT SPECIES PALETTE FOR RIPARIAN FOREST AND UPLAND RIPARIAN FOREST

30% DESIGN

NOTE: PLANSET CONTENT COLOR-DEPENDENT; PLANSET TO BE PLOTTED IN FULL COLOR

original size sheet This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD and shall not be reused in whole or in part for any other project without GHD's written authorization. © 2020 GHD



	(=)	H. T. HARVEY & ASSOCIATES
GHD	6	Ecological Consultants
GHD Inc. 2235 Mercury Way Suite		
Santa Rosa California 95 T 1 707 523 1010 F 1 7		/ www.ghd.com

rawn C. PENNY	Designer C. PENNY	Client END
afting J. SVEHLA neck	Design S. ALLEN Check	Project HAN Title REV
oject anager J. SVEHLA	Date 12/3/2020	Project No. 11
is document shall not be used for		Original Size

DANGERED HABITATS CONSERVANCY NSON RUSSIAN RIVER FLOODPLAIN RESTORATION PROJECT VEGETATION TYPICAL SECTION

ANSI D Sheet No. C-402 Sheet 20 of 20