Energy Project Analysis Firm Offer Proposal Main Office

05/28/2025

Prepared for:

Dale Roberts
Principal Engineer

Sonoma Water


Prepared by:

Tim McDuffie PE





SCALE MICROGRIDS



Consolidated Load Analysis

Load Profile Analysis

Peak Load 196 kW

Average Load 65 kW


Annual Electricity Usage 571,216 kWh

Projected PG&E Rate B-10

Projected Annual PG&E Costs \$227,604

Proj. Cost per kWh (PG&E) \$0.398

Load Profile Graph



Combined Load Profile for

Main Meter: 1009885172 Electric Vehicle Meter: 1010261710 Sub Meter: 1005720717

Asset Sizing and Footprint

Savings Plus Resiliency

Peak Load 196kW

Solar PV (kW DC) 356.4 Fixed Tilt

Energy Storage (kW/kWh) 196* / 2,121

Energy Resilience on Peak 72+ hours Day (July 2nd, 2024) at 100% Load

Microgrid Switchgear & Included Controller

^{* 530}kW Unit derated to meet incentive requirements





(1) Tesla Megapack 530 kW / 2121 kWh 30'W x 6' D x 9' H





Preliminary Solar Layout

Economics

Summary					
	20 Year Service Agreement Demolition Included				
Upfront Cost	\$0				
Tax Credits and Incentives	\$0				
Operations & Maintenance Cost	\$0				
Yr-1 MSA/PPA Cost	(\$266,000) \$230,194				
Yr-1 Utility Savings					
Yr-1 REC's	\$3,475				
Yr-1 Avoided Genset Cost	\$260,000				
Yr-1 Net Savings	\$227,668				
Cumulative Net Savings	\$917,705*				
Net Present Value	\$381,558				
Payback Period (Yrs)	Instant*				

^{*}Net Positive Bill Savings projected in Year 7, see ProForma

Assumptions

- 30% Federal Investment Tax Credit.
- The economics include an allowance for microgrid switchgear installation.
- Sonoma Clean Energy Evergreen Rates used
- Solar Billing Program credit applied for exports (\$0.025/kVVh)
- PWRPA Renewable Energy Credits included (\$0.005/kWh)
- Escalators used in economics are as follows:
 - Energy Charges: 5 %
 - Demand Charges: 5%
 - Discount Rate: 8%


- Demolition price = \$357,800, includes:
 - Existing Rooftop PV Array
 - Existing Array Cabling
 & Abandoned Conduits
 (WBE)
 - Existing Equipment
 Yard Enclosure
 - Existing PV Equipment within Equipment Yard
 - Existing PV Disconnect within Electrical Room
- Both estimates include the following adders:
 - New generator camlock panel
 - New wall around BESS
 - Meter consolidation
 - > 150' underground feeder to BESS

Pro-Forma

20 Year Service Agreement With Demolition								
	Cumulative	Annual	Electricity	VP-Committees and paid to their		Avoided	Avoided	
Year	Impact	Impact	Savings	REC's	MSA Costs	Capex	Opex	
Totals	\$917,705	\$917,705	\$7,471,020	\$88,757	(\$7,147,520)	\$250,000	\$255,447	
0	\$250,000	\$250,000	\$0	\$0	\$0	\$250,000	\$0	
1	\$227,668	(\$22,332)	\$230,194	\$3,475	(\$266,000)		\$10,000	
2	\$208,816	(\$18,852)	\$241,316	\$3,561	(\$273,980)		\$10,250	
3	\$193,747	(\$15,069)	\$252,973	\$3,651	(\$282,199)		\$10,506	
4	\$182,782	(\$10,965)	\$265,190	\$3,742	(\$290,665)		\$10,769	
5	\$176,262	(\$6,519)	\$277,993	\$3,835	(\$299,385)		\$11,038	
6	\$174,551	(\$1,712)	\$291,410	\$3,931	(\$308,367)		\$11,314	
7	\$178,030	\$3,479	\$305,471	\$4,029	(\$317,618)		\$11,597	
8	\$187,107	\$9,077	\$320,206	\$4,130	(\$327,146)		\$11,887	
9	\$202,212	\$15,105	\$335,648	\$4,233	(\$336,961)		\$12,184	
10	\$223,801	\$21,589	\$351,831	\$4,339	(\$347,070)		\$12,489	
11	\$252,357	\$28,556	\$368,789	\$4,448	(\$357,482)		\$12,801	
12	\$288,390	\$36,033	\$386,560	\$4,559	(\$368,206)		\$13,121	
13	\$332,441	\$44,051	\$405,182	\$4,673	(\$379,252)		\$13,449	
14	\$385,083	\$52,641	\$424,696	\$4,790	(\$390,630)		\$13,785	
15	\$446,918	\$61,836	\$445,145	\$4,910	(\$402,349)		\$14,130	
16	\$518,588	\$71,670	\$466,574	\$5,032	(\$414,419)		\$14,483	
17	\$600,767	\$82,179	\$489,028	\$5,158	(\$426,852)		\$14,845	
18	\$694,170	\$93,403	\$512,557	\$5,287	(\$439,657)		\$15,216	
19	\$799,550	\$105,380	\$537,212	\$5,419	(\$452,847)		\$15,597	
20	\$917,705	\$118,155	\$563,046	\$5,555	(\$466,433)		\$15,987	

SCALE MICROGRIDS

PG&E Tariffs Compound Annual Growth Rate (CAGR)



Appendicies

SCALE

SCALE MICROGRIDS

Proposed Racking Design

- 5 Degree Tilt
- Leaf-blower accessible
- Offset from rooftop to allow for drainage
- Space to walk in between rows
- Wind guards may be needed to prevent upward forces from wind, but do not impede drainage

Additional Information https://www.panelclaw.com/clawfr/#clawfr5

PANELCLAW





Engineered for Speed

- Single M6 bold hardware kit
- No tool module attachment method
- 90 degree single-module tilt-up feature
 Flexible order of operations installation
- riexible order or operations installation process allows for optimized coordination of building trades on the roof
- · Integrated roof protection pads
- 6.9"+ access ways between modules
- . Only 1 ground lug required per array

CONFIDENTIAL



Full Turnkey Microgrid Services Agreement (MSA) What's Included?



ENGINEERING & DESIGN



PERMITTING & INTERCONNECTION



CONSTRUCTION



FINANCING



ASSET MANAGEMENT



EQUIPMENT REPLACEMENT



OPERATIONS & MAINTENANCE



PERFORMANCE OPTIMIZATION

Project References



Entity: Goleta Water District

Contact Person: Shannon Eminhizer, Project Lead

Phone Number: 805-879-4665

Email Address: seminhizer@goletawater.com

Project Description: Installation of a 250kW / 1,000 kWh battery powered

microgrid at GWD's Water Treatment Plant

Date of Completion: November 11, 2024



Ribbon Cutting at Goleta Water District WTP

Gallaudet University

Contact Person: Dave Good, CEM, LEED-AP BD+C | Director, Energy, Utilities, and Sustainability

er: 202-651-5758

Phone Number:

Email Address: david.good@gallaudet.edu

Project Description:

Campus-wide microgrid consisting of 1.7MW of community solar, 1.7MW / 2.6MWh of batteries and 4.5MW

of Combined Heat and Power

Date of Completion:

January 1, 2025



GALLAUDET

Entity:

Entity:

Origo Investments

Contact Person:

Adam Hayner

Phone Number:

424-258-4995

Email Address:

adam.hayner@origoinvestments.com

Project Description:

Installation of a fully off-grid microgrid to support their cold storage facility in Madera, CA. Project consists of

2.4 MW of Solar, 2.4 MW/ 4.8 MWh of batteries, and 4.8 MW of Natural Gas generation.

Date of Completion:

June 2023